

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-20759-00-00
Spot: SWSE Sec/Twnshp/Rge: 29-26S-20E
653 feet from S Section Line, 1925 feet from E Section Line
Lease Name: CAMPBELL Well #: 7
County: ALLEN Total Vertical Depth: 854 feet

Operator License No.: 4485
Op Name: VERDE OIL COMPANY
Address: 7702 BROADWAY ST., STE 200
SAN ANTONIO, TX 78209

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 2.375 | 854 | | 112 SX |
| SURF | 7 | 20 | | 5 SX |

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/24/2016 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: JIM DENYER Company: Phone: (620) 754-3800

Proposed Plugging Method: Run 1" tubing to PBTD. Circulate cement to surface. Pull tubing & fill displacement from surface. Well will be plugged from PBTD to surface.

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed: 03/24/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing that was cemented inside the 7" surface casing to TD. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled the 1" pipe out of the casing and topped the well off with cement. A total of 29 sacks of portland cement was reported used to plug this well.

Perfs:

| Top | Bot | Thru | Comments |
|--|-----|------|----------|
| 816 | 837 | | |
| RECEIVED KCC DIST # 3 MAY 24 2016 CHANUTE, KS RD | | | |

Remarks:

Plugged through: TBG

District: 03

Signed

E.C.R.S.
(TECHNICIAN)

KCC WICHITA

MAY 27 2016

RECEIVED

Form CP-2/3

no
6-13-16