

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22719-00-00
Spot: SWNENE Sec/Twnshp/Rge: 20-28S-4E
4612 feet from S Section Line, 940 feet from E Section Line
Lease Name: SMITH Well #: BE 8
County: BUTLER Total Vertical Depth: 3057 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2495		75 SX
SURF	8.625	212		150 SX

Well Type: SWD UIC Docket No: D24122.0 Date/Time to Plug: 04/29/2016 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/29/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG & TAGGED CEMENT @ 640', CONSOLIDATED OILWELL SERVICES
ESTABLISHED CIRCULATION, MIXED & PUMPED 70 SXS 60/40 POZMIX 4% GEL 2%
CC & 100#'S HULLS TO SURFACE. CEMENT CIRCULATED. SWEDGED INTO 5.5"
CSG & PUMPED 20 SXS, SIP 300#. PLUG DOWN 11:15 AM 4-29-2016.
CONSOLIDATED CEMENT TICKET #51206.

Perfs:

Top	Bot	Thru	Comments
2495	3057	OH	

Remarks: FAILED MIT / CASING LEAK @ 575' - 728.

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 20 2016

CONSERVATION DIVISION
WICHITA, KS

JK

Form CP-2/3

NO
6-13-16
CC UIC