

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-19237-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 31-23S-17E
3355 feet from S Section Line, 2455 feet from E Section Line
Lease Name: FRED ELLIS NORTH Well #: 1
County: WOODSON Total Vertical Depth: 950 feet

Operator License No.: 3728
Op Name: RJ ENERGY, LLC
Address: 22082 NE NEOSHO RD
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	950		100 SX
SURF	7	40		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2016 12:00 AM
Plug Co. License No.: 3728 Plug Co. Name: RJ ENERGY, LLC
Proposal Rcvd. from: JASON KENT Company: _____ Phone: (785) 448-4101

Proposed Plugging Method: Run down inside & outside and fill well to surface.

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 03/24/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report: _____ Perfs: _____

Ran 1" pipe down the inside of the 2.875" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.875" from TD to surface. Pulled the 1" pipe out of the casing. Ran 1" pipe down the backside of the 2.875" casing to 500'. Pumped and circulated cement through the 1" pipe from 500' to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 90 sacks of portland cement was reported used to plug this well.

RECEIVED
KCC DIST # 3
MAY 24 2016
CHANUTE, KS

RD

Remarks:
Plugged through: TBG

District: 03

Signed *[Signature]* E.C.R.S.
(TECHNICIAN)

KCC WICHITA
MAY 27 2016
RECEIVED

Form CP-2/3
no
6-13-16