

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-207-20886-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 31-23S-17E  
3040 feet from S Section Line, 1755 feet from E Section Line  
Lease Name: FRED ELLIS NORTH Well #: 7  
County: WOODSON Total Vertical Depth: 950 feet

Operator License No.: 3728  
Op Name: RJ ENERGY, LLC  
Address: 22082 NE NEOSHO RD  
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	950		100 SX
SURF	7	40		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/21/2016 12:00 AM  
Plug Co. License No.: 3728 Plug Co. Name: RJ ENERGY, LLC  
Proposal Rcvd. from: JASON KENT Company: \_\_\_\_\_ Phone: (785) 448-4101

Proposed Plugging Method: Run down inside & outside and fill well to surface.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: NONE  
Date/Time Plugging Completed: 03/21/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2.875" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.875" from TD to surface. Pulled the 1" pipe out of the casing. Ran 1" pipe down the backside of the 2.875" casing to 500'. Pumped and circulated cement through the 1" pipe from 500' to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 72 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED  
KCC DIST # 3  
MAY 24 2016  
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed

Ryan M. Duling E.C.R.S.  
(TECHNICIAN)

KCC WICHITA

MAY 27 2016

RECEIVED

Form CP-2/3

NO  
6-13-16