

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217


FORM CP-4

WELL PLUGGING RECORD

Kingman County. Sec. 9 Twp. 29S Rge. 7W ~~7E~~ ~~8W~~

Location as "NE/CNW/SW" or footage from lines NE SW
Lease Owner Graves Drilling Co., Inc.
Lease Name Lecklider Well No. 1
Office Address 505 Union Center Bldg., Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 11, 19 75
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced January 11, 19 75
Plugging completed January 11, 19 75
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above Section Plot

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

PERMITS	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	221'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,200 feet (rotary total depth) to 210 feet. Set plug at 210 feet and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 210 feet to 40 feet. Set solid plug at 40 feet and cemented to cellar with 15 sacks cement, two sacks cement in rathole.

Plugging operations accomplished utilizing Allied Oil Well Cementing pump truck through 4 1/2 inch drill pipe.


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 No. Main, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (Agent of owner ~~XXX XXX XXX XXX~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 No. Main, Wichita, Kansas 67202
(Address)

Subscribed and Sworn to before me this 14th day of January, 19 75



June 30, 1978
Elsie Willison - Notary Public.

15-095-20385-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Graves Drilling Co., Inc.**

SEC. **9** T. **29S** R. **7W**
LOC. **NE SW**

FARM **Lecklider** NO. **1**

TOTAL DEPTH **4,200'**

COUNTY **Kingman**
KANSAS


COMM. **January 3, 1975**

COMP. **January 11, 1975**

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED



CASING

20	10	
15	8-5/8"	221' cemented w/215 sxs cement ELEVATION 1,627' KB
12	6	
13	5	

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	165'
Shale and Red Bed	1,126'
Lime and Shale	4,200'
Rotary Total Depth	4,200'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.


H-30, INC.

Dean Britting

Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 14th. day of January, 1975.



Elsie Willison

Elsie Willison - Notary Public

My Commission Expires:

June 30, 1978

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1975

CONSERVATION DIVISION
Wichita, Kansas