


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 36 Twp. 29S Rge. (E) 6 (W)

Location as "NE/CNW/SW" or footage from lines NW SE NE
Lease Owner Rains & Williamson Oil Co.
Lease Name GRABER Well No. 1
Office Address 1425 Wichita Plaza - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-4 19 63
Application for plugging filed 11-4 19 63
Application for plugging approved 11-4 19 63
Plugging commenced 11-4 19 63
Plugging completed 11-4 19 63
Reason for abandonment of well or producing formation No oil or gas found in commercial quantities
If a producing well is abandoned, date of last production --- 19 --
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Archie Elving, Pratt, Kansas
Producing formation None Depth to top -- Bottom -- Total Depth of Well 4500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	299'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud to 290' of base of cellar. Set first plug with 1/4 sack hulls, cemented through drill pipe with 25 sacks cement. Filled hole with rotary mud to 40' of base of cellar. Set plug, 1/4 sack hulls, and capped with 15 sacks cement. Plugging completed at 7:45 P.M., 11-4-63.

RECEIVED
STATE CORPORATION COMMISSION

11-07-63 NOV 7 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza Building - Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Wilson Rains, Partner (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains
1425 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of November, 19 63

My commission expires November 8, 1966 Sherry Gish Notary Public.

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co.
and Mull Drilling Co., Inc.
NO. 1 GRABER
NW SE NE Sec. 36-29S-6W
Kingman County, Kansas

CONTRACTOR: Rains & Williamson Oil
COMMENCED: 10-25-63
COMPLETED: 11-4-63

Remarks: Set 8-5/8" casing at
299' w/150 sacks cement

Formations

Clay, Sand & Shale	300'
Red Bed and Shale	500'
Shale	940'
Anhydrite	950'
Shale	974'
Anhydrite	985'
Shale and Lime	1255'
Shale and Shells	1368'
Lime	1915'
Shale - Lime Streaks	2275'
Shale and Lime	2775'
Sand	2895'
Lime	3144'
Shale and Lime	3295'
Shale	3320'
Lime	3775'
Lime and Shale	3836'
Lime	4106'
Lime and Shale	4130'
Lime (Cherty)	4162'
Lime	4399'
Shale	4382'
Lime	4475'
Shale	4485'
Lime	4500'
Rotary Total Depth (D&A)	4500'

RECEIVED
STATE CORPORATION COMMISSION

NOV 7 1963


CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true
and correct to the best of our
knowledge and belief.

RAINS & WILLIAMSON OIL CO.


Wilson Rains-Partner

Subscribed and sworn to before me, a
Notary Public in and for the State of
Kansas, County of Sedgwick, this 6th
day of November, 1963.


Sherry Gish-Notary Public

My Commission Expires:
November 8, 1966