


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Kingman County, Sec. 16 Twp. 29 Rge. 8W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner Pet-Ex Company, Inc.
Lease Name Clouse Well No. 1
Office Address 702 Union Center Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 19____
Plugging completed March 12, 19 60
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4530' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T. D. 4530' - S. P. 8 5/8" 248' Cwc 175 sacks
Heavy mud to 240' set plug used 1/4 sack hulls
18 sacks cement through drill pipe, mud to 40'
set plug used 1/4 sack hulls and 10 sacks cement
to base of cellar.

Bridge rat hole used hulls and two sacks cement
below cultivation depth.

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1966
WICHITA, KANSAS
4-11-1966

Name of Plugging Contractor Twin Drilling Co., Inc. (If additional description is necessary, use BACK of this sheet)
Address 1732 Wichita Plaza Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Almeda Day (employee of ~~owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Almeda Day
1732 Wichita Plaza Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of April 19 66

My commission expires September 29, 1968

James S. Hicke
Notary Public.

WELL LOG

Operator: Pet-Ex Co.
300 Insurance Building
Wichita, Kansas

Well: Clouse #1
Location: SW SW SE
Section 16-29S-8W
Kingman County, Kansas

Contractor: Twin Drilling, Inc.
1005 Central Building
Wichita, Kansas

Commenced: 2-26-60
Completed: 3-12-60

Casing: 8 5/8" 251' Surface
W/165 sax

Surface	40	Shale & Chert	4462
Sand & Shale	100	Lime	4493
Shale & Shells	251	Lime & Sand	4530
Red Bed	960		
Shale & Lime Shells	1413	Rotary T. D. 4530'	
Shale & Shells	1500		
Lime & Shale	1635	D & A	
Lime	1805		
Lime & Shale	2185		
Lime	2343		
Shale & Lime Streaks	2602		
Lime & Shale	2820		
Shale & Lime Streaks	2860		
Lime	2905		
Lime & Shale Breaks	3050		
Lime & Shale	3090		
Lime	3140		
Lime & Shale	3330		
Shale & Sand	3423		
Lime	3895		
Shale & Lime	3920		
Lime & Shale	3984		
Lime	4075		
Lime & Shale	4145		
Chert	4150		
Cherty Chat	4170		
Chert & Chat	4269		
Lime	4291		
Chert & Lime	4321		
Shale	4393		

RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1960
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

The undersigned, TWIN DRILLING, INC., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

TWIN DRILLING, INC.

By: *Alameda Day*

Subscribed and sworn to before me
this 22nd day of March, 1960.

James A. Nichols
Notary Public

My commission expires
September 29, 1960.