

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-21800-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 26-18S-10W  
990 feet from S Section Line, 4924 feet from E Section Line  
Lease Name: GODFREY Well #: 5  
County: RICE Total Vertical Depth: 3320 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3318	2400	125 SX
SURF	8.625	262		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/11/2016 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS INC Phone: (785) 261-9653

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/11/2016 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SANDED PERFS TO 3150' AND CAPPED WITH 5 SX'S CEMENT. CUT CASING OFF AT 2400' AND PULLED TO 1200' AND PUMPED 35 SX'S CEMENT WITH 3% CC AND 150 #'S COTTON HULLS, PULL CASING TO 850' AND WAIT 1 HOUR. TAGGED CEMENT AT 900' WITH SWAB BAR. PUMP 35 SX'S AND 100#'S COTTON HULLS AT 850', PULL CASING TO 312' AND CIRCUALTE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3261	3264		CSG

Remarks: 60-40 POZ, 3% GEL. QUALITY OILWELL CEMENTING TICKET #1346. TA - N.O.V. LETTER SENT ON THIS WELL.

Plugged through: CSG

District: 02

Signed \_\_\_\_\_  
Received \_\_\_\_\_  
KANSAS CORPORATION COMMISSION

*Virgil Clothier*  
(TECHNICIAN)

MAY 25 2016

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*W*  
*6-13-16*