

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-173-19081-00-01
Spot: SWSEENENW Sec/Twnshp/Rge: 16-25S-1E
4269 feet from S Section Line, 3077 feet from E Section Line
Lease Name: GOODRICH Well #: 109 W
County: SEDGWICK Total Vertical Depth: 2780 feet

Operator License No.: 6804
Op Name: LACHENMAYR OIL LLC
Address: PO BOX 526
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2779		100 SX
SURF		151		
SURF	8.625	161		150 SX

Well Type: EOR UIC Docket No: E13037.2 Date/Time to Plug: 02/09/2016 9:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: JOHN LACHENMAYR Company: LACHENMAYR OIL, INC. Phone: (316) 284-1991

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 02/10/2016 12:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

SAND BACK FOR BOTTOM PLUG, TAGGED TOP OF SAND AT 2670'. CAPPED WITH 4 SX OF CEMENT WITH BAILER. WIRE LINE TAGGED TOP OF CEMENT AT 2478'. PERORATED 4.5" PRODUCTION CASING AT 260' TO 261' WITH 4 SHOTS. MIXED 104 SX OF 60/40 POZ-MIX W/4% GEL, CIRC. CEMENT TO SURFACE. OPERATOR CAME BACK AND CUT OFF CASING BELOW GROUND AFTER A FEW DAYS. PLUG JOB COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2722	2727	TBG	

Remarks:

Plugged through: TBG

District: 02

Signed

Daniel J. Fox
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
MAY 20 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3
no 6-13-16 cc a/c

✓