

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-079-00463-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 8-23S-3W  
330 feet from N Section Line, 330 feet from W Section Line  
Lease Name: SHORT Well #: 4  
County: HARVEY Total Vertical Depth: 3385 feet

Operator License No.: 7116  
Op Name: KANTOR OIL COMPANY, LLC  
Address: 15 W 6TH ST STE 2601  
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3300		
PROD	5.5	3352		100 SX
SURF	8.625	300		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2016 12:00 AM  
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.  
Proposal Rcvd. from: LARRY RESSLER Company: \_\_\_\_\_ Phone: (620) 664-0597

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/29/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3300' W/4 SKS. OF CEMENT ON TOP OF PLUG W/DUMP BALER. PERFORATED 5.50 @ 600 FT. & 350 FT. W/4 SHOTS. TIHW TUBING TO 600 FT. MIXED AND PUMPED 35 SACK COMMON CEMENT PLUG W/ 3% CC AND 150# HULLS. TOHW TUBING. WAIT 1.5 HOURS. RIHW WIRELINE AND TAG PLUG @ 400 FT. TIHW TUBING TO 350 FT. MIX AND PUMP 175 SACKS OF 60-40 POZ CEMENT. CEMENT DID CIRCULATE BETWEEN 5.50 AND 8.625. 5.50 CASING WAS FULL OF CEMENT. CHECKED PLUG TWO DAYS LATER. ANNULUS REMAINED FULL. CEMENT FELL 10 FT. IN 5.50. TOPPED OFF 5.50 W/ 2 SKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3352	3385		

Remarks: COPELAND CEMENTING OUT OF BURRTON. CLASS A USED FOR BOTTOM SALT PLUG. 60/40 4% POS MIX. REST OF PLUGGING. TICEKT #37442.

Plugged through: CSG

District: 02

Signed B. J. Hope

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAY 23 2016

CONSERVATION DIVISION  
WICHITA, KS

NO  
6-13-16  
Form CP-2/3