

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-20011-00-01  
Spot: SWSWSE Sec/Twnshp/Rge: 22-30S-4E  
471 feet from S Section Line, 2198 feet from E Section Line  
Lease Name: DONLEY (FEASTER) Well #: 1  
County: COWLEY Total Vertical Depth: 2925 feet

Operator License No.: 31302  
Op Name: JONES & BUCK DEVELOPMENT, LLC  
Address: PO BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2924	230	150 SX
SURF		203		
SURF	8.625	205		175 SX

Well Type: EOR UIC Docket No: E13624.1 Date/Time to Plug: 04/14/2016 8:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: JOHN ELMORE Company: ELMORES, INC. Phone: (620) 725-3636

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/15/2016 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG CIRCULATION VARIOUS BRIDGES IN WELL FROM 2100'-2835'. W/TBG @ 2835' ELMORES ESTABLISHED CIRCULATION, CIRCULATED 1 SX GEL PLUG & MIXED & PUMPED 10 SXS CLASS A COMMON FOLLOWED BY 1 SX GEL PLUG & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 2710'. RIH ON WIRELINE CUT CASING @ 600', 300', & 230', LAYED DOWN 230' 4.5" CASING (6 JOINTS). RIH W/TBG @ 250', ELMORES ESTABLISHED CIRCULATION, MIXED & PUMPED 85 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. 4-15-2016, TAGGED CEMENT @ 60', ELMORES MIXED & DUMPED 15 SXS TO SURFACE. P & A COMPLETE 4-15-2016.

Perfs:

Top	Bot	Thru	Comments
2852	2854		CSG

Remarks: DOCKET #E-13,624

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAY 20 2016  
CONSERVATION DIVISION  
KS

Form CP-2/3

Mo  
6-13-16  
CC UIC

JK