

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-011-23597-00-00
Spot: SESESW Sec/Twnshp/Rge: 6-25S-24E
330 feet from S Section Line, 2310 feet from W Section Line
Lease Name: GROSS Well #: 14-6
County: BOURBON Total Vertical Depth: 600 feet

Operator License No.: 33397
Op Name: RUNNING FOXES PETROLEUM INC.
Address: 48 INVERNESS CT E. SUITE 120
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	600		68 SX
SURF	8.625	21		12 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2013 12:00 AM
Plug Co. License No.: 34430 Plug Co. Name: CST OIL & GAS CORPORATION
Proposal Rcvd. from: CHUCK HUTTON Company: _____ Phone: (620) 829-5307

Proposed
Plugging
Method:

Cement to surface

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 02/19/2013 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 4.5" casing to TD. Pumped 10 sacks portland cement through the 1" pipe inside the 4.5" casing at TD. Pulled 1" pipe up to 175'. Pumped and circulated cement from 175' to surface. Pulled the 1" pipe out of the casing and topped the well off with cement. A total of 25 sacks of portland cement was reported used to plug this well.

RECEIVED
KCC DIST # 3
MAY 24 2016
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed Ryan M. Dulig E.C.A.S.
(TECHNICIAN)

KCC WICHITA
MAY 27 2016
RECEIVED

Form CP-2/3

no
6-13-16