

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-30944-00-00

Spot: SENE SW

Sec/Twnshp/Rge: 14-34S-14E

1597 feet from S Section Line, 2980 feet from E Section Line

Lease Name: SMOTHERMON

Well #: 24RBN

County: MONTGOMERY

Total Vertical Depth: 620 feet

Operator License No.: 33297

Op Name: ROCKIN BAR NOTHIN RANCH, INC.

Address: 2339 COUNTY RD 2800
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	620		105 SX
SURF	7	22		15 SX

Well Type: DH

UIC Docket No:

Date/Time to Plug: 02/24/2006 12:00 AM

Plug Co. License No.: 33961

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC

Proposal Rcvd. from: BRANDON W OWENS

Company:

Phone: (620) 330-3454

Proposed Plugging Method: 50' cement and plug on bottom, 50' plug at 400', 250' to surface, gel spacers

Plugging Proposal Received By: RON ROWE

WitnessType: NONE

Date/Time Plugging Completed: 02/24/2006 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran tubing to TD gelled hole and spotted 50' plug. Pulled up to 400' and spotted 50' plug. Pulled up to 250' and circulated cement to surface. Pulled tubing and topped well off. A total of 80 sacks of cement were used to plug this well.

RECEIVED
KCC DIST # 3
MAY 24 2016
CHANUTE, KS

DS

Remarks:

Plugged through: TBG

District: 03

Signed

Duane A Sims

(TECHNICIAN)

KCC WICHITA

MAY 27 2016

RECEIVED

Form CP-2/3

20
6-13-16