

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-20973-00-00
Spot: SESESW Sec/Twnshp/Rge: 2-20S-3W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HERROLD Well #: 1
County: MCPHERSON Total Vertical Depth: 3107 feet

Operator License No.: 6523
Op Name: SCHMIDT, KERMIT AND TRACY SCHM
Address: 308 WESTLANE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
MSCC	2.275	300	300	
PROD	5.5	3106		65 SX
SURF	8.625	225		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2016 4:25 PM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: KERMIT SCHMIDT Company: SCHMIDT, KERMIT & TRACY SCH Phone: (620) 241-1255

Proposed Plugging Method: SAND DROM 3106' TO 2980'. CIRCUALTE CEMENT TO SURFACE FROM 300'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2016 4:25 PM KCC Agent: JERRY SPARLING

Actual Plugging Report:

12 SX SAND FROM 3106' TO 2980'. CONSOLIDATED TICKET #52109. 60 SX 60/40 CEMENT 4% GEL THROUGH 1 INCH DOWN BACKSIDE FROM 300' TO SURFACE. 40 SX 60/40 CEMENT 4% GEL WITH 2% COTTONSEED HULLS THROUGH 2 3/8" TUBING FROM 300' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3027	3051	OH	

Remarks: CONSOLIDATED WELL SERVICES WERE CONTRACTED FOR CEMENT. LACK OF LEASE / 10 YR TA

Plugged through: OH

District: 02

Signed Jerry Sparling
(TECHNICIAN)

KCC WICHITA
JUN 02 2016
RECEIVED

Form CP-2/3
no
6-13-16

JK