

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21294-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 17-27S-17W  
4467 feet from S Section Line, 2270 feet from E Section Line  
Lease Name: SPARKE Well #: 1-17  
County: KIOWA Total Vertical Depth: 4800 feet

Operator License No.: 4976  
Op Name: SOUTHWEST OPERATING COMPANY  
Address: 10551 BARKLEY STE # 108 PO BOX 25  
OVERLAND PARK, KS 66212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4634		WITH 2 SX CMT
PROD	4.5	4799	0	WITH 200 SX CMT
SURF	8.625	398		WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/17/2016 9:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: ROGER BROWN Company: FISCHER WELL SERVICE Phone: (785) 628-3837

Proposed Plugging Method: CIBP @ 4600' WITH 2 SX CMT. CUT & PULL CASING. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 450' WITH 50 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/17/2016 11:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4634' WITH 2 SX CMT. PRESSURE TESTED THE CASING & IT HELD. PERFORATED AT 1200' & 450'. RAN TBG TO 1200' & PUMPED 50 SX CMT. PULLED TBG TO 450' & PUMPED 40 SX CMT CIRCULATING CMT UP THE PRODUCTION CASING. PULLED TBG & TIED ONTO THE 4 1/2" CASING & PUMPED 40 SX CMT. CIRCULATION WAS GOOD BUT ONLY RETURNED WATER. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 100#.

Perfs:

Top	Bot	Thru	Comments
4684	4712		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED  
MAY 19 2016  
KCC DODGE CITY

Signed [Signature]  
Received  
KANSAS CORPORATION COMMISSION SA (TECHNICIAN)  
MAY 25 2016  
CONSERVATION DIVISION  
WICHITA KS

Form CP-2/3

NO  
6-13-16