

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-20454-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 9-33S-19W  
4879 feet from S Section Line, 3681 feet from E Section Line  
Lease Name: FITZWATER Well #: 2A-9  
County: COMANCHE Total Vertical Depth: 5320 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5090		WITH 10 SX CMT
COND	13.375	217		
PROD	4.5	5320	1216	WITH 200 SX CMT
SURF	8.625	637		WITH 500 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2016 12:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5090' WITH 10 SX CMT. PLUG AT 1020' WITH 50 SX CMT. PLUG AT 700' WITH 80 SX CMT. PLUG AT 300' TO SURFACE WITH 85 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/23/2016 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5090' WITH 10 SX CMT ON TOP OF CIBP. 1ST PLUG AT 1020' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 85 SX CMT. 3RD PLUG AT 300' WITH 85 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5140	5190		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]  
KCC WICHITA (TECHNICIAN)

RECEIVED  
MAY 25 2016  
KCC DODGE CITY

RECEIVED  
JUN 03 2016

Form CP-2/3  
710  
6-13-16