

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-20442-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 8-33S-19W  
3630 feet from S Section Line, 990 feet from E Section Line  
Lease Name: ZIELKE Well #: 5-8  
County: COMANCHE Total Vertical Depth: 5330 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5094		WITH 10 SX CMT
PROD	5.5	5305	1203	WITH 200 SX CMT
SURF	8.625	632		WITH 500 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/26/2016 10:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Set 5" CIBP @ 5094'. Cir hole with mud & cap w/10 sks cement. ND BOP. Weld on pull sub, NU BOP with 5.5" rims, cut & pull free pipe. Spot the following cement plugs: @ 700' - with 80 sks cement. @ 330' to surface with 90 sks cement. Cut & Cap well. Dig up rig anchors

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE  
Date/Time Plugging Completed: 05/26/2016 11:30 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SET CIBP @ 5094' WITH 10 SX CMT. RUN IN HOLE WITH TBG. 1ST PLUG AT 1000' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 80 SX CMT. 3RD PLUG AT 330' CIRCULATE TO SURFACE WITH 90 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5144	5198		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SEND\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
MAY 31 2016  
KCC DODGE CITY

KCC WICHITA  
JUN 03 2016  
RECEIVED

Form CP-2/3

no  
6-13-16