

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23892-01-00
Spot: SESWSWSE Sec/Twnshp/Rge: 13-35S-10W
251 feet from S Section Line, 2257 feet from E Section Line
Lease Name: ZOEY Well #: 1-13H
County: BARBER Total Vertical Depth: 4795 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4920		WITH 50 SX CMT
COND	20	90		WITH 12 SX CMT
	11 7	5423	1230	WITH 310 SX CMT
	11 4.5	8450		310 sx cement
SURF	9.625	960		WITH 490 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/13/2016 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: CLIFF LINDSEY Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4896' WITH 50 SX CMT. PLUG AT 1020' WITH 75 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/13/2016 11:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4920'. LOAD HOLE WITH MUD & SPOT 50 SX CMT ON TOP OF CIBP THROUGH TBG. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 1000' WITH 75 SX CMT. 3RD PLUG AT 425' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
7971	8310		
7549	7888		
7128	7467		
6738	8310		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
MAY 19 2016
KCC DODGE CITY

Signed [Signature]
KCC WICHITA (TECHNICIAN)
SA JUN 03 2016

RECEIVED

700
6-13-16
Form CP-2/3