

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-21711-00-00  
Spot: SENENE Sec/Twnshp/Rge: 19-7S-17W  
4290 feet from S Section Line, 330 feet from E Section Line  
Lease Name: LIEBENAU Well #: 8  
County: ROOKS Total Vertical Depth: 3325 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>32278</u>	COND	13.375	128		130 sx
Op Name: <u>TENGASCO, INC.</u>	PROD	5.5	3323		150 SX
Address: <u>1327 NOOSE RD PO BOX 458</u> <u>HAYS, KS 67601</u>	SURF	8.625	1193		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2016 8:30 AM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO INC. Phone: (78) 525-6374

Proposed Plugging Method: Orderd 250 sx 60/40 pozmix 4% gel cement, 15 sx gel and 500 # hulls.  
Production perforations: 3229' - 3237'  
Aug 1985- squeezed down annulus w/150 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/12/2016 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3250' and pumped 15 sx gel followed by 50 sx cement w/300 # hulls. Pulled tubing to 1240' and pumped 150 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/10 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 1/4 bbl. Pressured to 300 psi.

GPS: 39.43422N -099.25084W

Perfs:

Top	Bot	Thru	Comments
3229	3237		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1861

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

KCC WICHITA

MAY 20 2016

MAY 31 2016

RECEIVED

Form CP-2/3

*720*  
*6-13-16*