

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-20264-00-00
Spot: NWNWSWSW Sec/Twnshp/Rge: 3-31S-8E
1099 feet from S Section Line, 5157 feet from E Section Line
Lease Name: DENTON Well #: 9
County: ELK Total Vertical Depth: 2695 feet

Operator License No.: 3359
Op Name: T & R OIL COMPANY, A GENERAL PA
Address: PO BOX 92
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2688		200 SX
SURF	8.6	98		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: ROGER PATTESON Company: _____ Phone: (620) 647-3352

Proposed Plugging Method: Will place 10 sacks cement on bottom, 5 sacks at 1200 ft. and then cement from 550 ft. to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 04/08/2016 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" 1860' gelled hole and spotted 10 sack plug. Pulled 1" out and perforated casing at 1200' and 550'. Ran 1" into 1200' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 151 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
MAY 24 2016
CHANUTE, KS

DS

Remarks:

Plugged through: TBG

District: 03

Signed Duane A Sims
(TECHNICIAN)

KCC WICHITA
MAY 27 2016
RECEIVED

Form CP-2/3
20
6-13-16