

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-079-00363-00-00
Spot: SENESE Sec/Twnshp/Rge: 34-24S-2E
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: LUCY DUBOIS Well #: 6
County: HARVEY Total Vertical Depth: 2841 feet

Operator License No.: 34381
Op Name: URBAN OIL AND GAS GROUP LLC
Address: 1000 E 14TH ST SUITE 300
PLANO, TX 75074

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2500		CAPPED W/2 SKS
PROD	5.5	2840		50 SX
SURF	8.625	200		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/12/2016 8:00 AM
Plug Co. License No.: 35172 Plug Co. Name: LEE'S WELL SERVICE LLC
Proposal Rcvd. from: DAVID FRANKS Company: URBAN OIL & GAS GROUP Phone: (972) 543-8800

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/12/2016 11:30 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) GEMINI WIRELINE RAN IN AND SET A CIBP AT 2500' AND CAPPED W/2 SKS CEMENT. 2) WIRELINE RAN BACK IN AND PERFORATED 5.5" CASING W/ 2 SHOTS. 3) TIED INTO 5.5" CASING, LOADED HOLE AND CIRCULATED. CONSOLIDATED PUMPED APPROX. 92 SKS OF 60/40 4% CEMENT W/ 2% CACL. CIRCULATED CEMENT TO SURFACE. 5/13/2016 CHECKED TOP PLUG, CEMENT DOWN 8' IN CASING AND ON BACKSIDE. PIPE CUT OFF BELOW GROUND LEVEL AND BURIED.

Perfs:

Top	Bot	Thru	Comments
2543	2552		CSG

Remarks: CEMENTING COMPLETED BY CONSOLIDATED OIL WELL SERVICE, EL DORADO, KS. TICKET #: 51255. PLUGGED DUE TO DENIED TA FOR HIGH FLUID LEVEL.

Plugged through: CSG

District: 02

Signed Jonathan Hill (TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 23 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3
6-13-16