

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-23942-00-00
Spot: NENESENE Sec/Twnshp/Rge: 30-33S-13E
3864 feet from S Section Line, 272 feet from E Section Line
Lease Name: BALLARD G Well #: 5
County: CHAUTAUQUA Total Vertical Depth: 788 feet

Operator License No.: 4448
Op Name: PERKINS OIL ENTERPRISES, INC.
Address: PO BOX 707
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	788		100 SX
SURF	7	63		2 SX

Well Type: SWD UIC Docket No: D20204.0 Date/Time to Plug: 01/18/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: KEVIN WARDLOW Company: Phone: (620) 330-3666

Proposed
Plugging
Method:

LAY WELL OUT, RUN TUBING IN TO BOTTOM & PUMP CEMENT TO TOP, LAY OUT TUBING & TOP OFF

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 01/18/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 780' gelled hole and spotted 10 sack plug. Pulled up to 500' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 51 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
598	618		

RECEIVED
KCC DIST # 3
MAY 24 2016
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

KCC WICHITA
MAY 27 2016
RECEIVED

Form CP-2/3

20
6-13-16
CC AIC