

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-21879-00-02  
Spot: NESESW Sec/Twnshp/Rge: 20-10S-25W  
1017 feet from S Section Line, 3128 feet from E Section Line  
Lease Name: ROHLEDER Well #: 1  
County: GRAHAM Total Vertical Depth: 4090 feet

Operator License No.: 5205  
Op Name: MID-CONTINENT ENERGY CORP.  
Address: 105 S BROADWAY STE 360  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2050		
PROD	4.5	4089		125 SX
SURF	8.625	248		170 SX

Well Type: SWD UIC Docket No: D24786.0 Date/Time to Plug: 05/19/2016 9:30 AM  
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.  
Proposal Rcvd. from: JEFF BURK Company: MID-CONTINENT ENERGY CORP. Phone: (316) 269-2015

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Squeezed at 2190' w/150 sx cement, 1500' w/300 sx cement, 1300' w/400 sx cement and 900' w/100 sx cement.  
CIBP set at 2050'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/19/2016 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Dug out the braaden head and found it to be full of cement. Well was re-completed and plugged back for Cedar Hill Disposal. Ran tubing to 1898' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 822' and pumped 70 sx cement. Had good cement returns to the pit. POOH. Pumped 10 sx cement to top off casing. Casing stayed full.

GPS: 39.16356 -100.13718

Perfs:

Top	Bot	Thru	Comments
4039	4043		
4015	4018		
1905	1925		

Remarks: QUALITY CEMENTING TICKET # 1540

Plugged through: TBG

District: 04

Signed

*Ray Dinkel*

KCC WICHITA

(TECHNICIAN)

CM

MAY 20 2016

MAY 31 2016

RECEIVED

Form CP-2/3

*no  
6-13-16  
CC WIC*