

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-21903-00-00
Spot: SESWSE Sec/Twnshp/Rge: 20-10S-25W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SCHAMBERGER Well #: 2
County: GRAHAM Total Vertical Depth: 4110 feet

Operator License No.: 5205 String Size Depth (ft) Pulled (ft) Comments
Op Name: MID-CONTINENT ENERGY CORP. PROD 4.5 4109 150 SX
Address: 105 S BROADWAY STE 360 SURF 8.6252 246 165 SX
WICHITA, KS 67202

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/18/2016 10:00 AM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: JEFF BURK Company: MID-CONTINENT ENERGY CORP. Phone: (620) 793-5976

Proposed Plugging Method: Ordered 330 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations at 3882' - 3884', 3892' - 3896', 3921' - 3923' and 3928' - 3932'
Anhydrite at 2190'
Port Collar at 1423' w/850 sx cement.
Alt II approved by district supervisor

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2016 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3980' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2591' and pumped 100 sx cement. Pulled tubig to 1200' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 0 sx cement. Shut in pressure 300 psi.

GPS: 39.16172 -100.13253

Perfs:


Top	Bot	Thru	Comments
3928	3932		
3921	3923		
3892	3896		
3882	3884		

Remarks: QUALITY CEMENT TICKET # 1967

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

KCC WICHITA

MAY 31 2016

RECEIVED

MAY 18 2016

Form CP-2/3

720
6-13-16