

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-02153-00-00  
Spot: NWNESESE Sec/Twnshp/Rge: 4-24S-18E  
1109 feet from S Section Line, 519 feet from E Section Line  
Lease Name: HOWLAND B Well #: 15Q  
County: ALLEN Total Vertical Depth: 900 feet

Operator License No.: 33783  
Op Name: MICHAEL DRILLING LLC  
Address: 1304 E ST PO BOX 402  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD 2		900		20 SX
SURF 7		20		5 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2016 12:00 AM  
Plug Co. License No.: 33783 Plug Co. Name: MICHAEL DRILLING LLC  
Proposal Rcvd. from: RICK MICHAEL Company: \_\_\_\_\_ Phone: (62) 096-7795

Proposed  
Plugging  
Method:

RUN 1" PIPE TO T.D. PUMP 10 SX CEMENT, PULL TO 500' PUMP 10 SX CEMENT, PULL TO 250' FILL TO SURFACE .RUN 1" DOWN BACK SIDE 250' FILL SURFACE.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/31/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 2" casing to TD. Pumped and circulated cement through the 2" pipe inside the 7" casing from TD to surface. Pulled the 1" pipe out of the 2" casing. Ran 1" pipe down the backside of the 2" casing inside the 7" casing to 400'. Pumped and circulated cement through the 1" and brought cement to surface. Pulled the 1" pipe out of the well. Topped the well off with cement. A total of 100 sacks of portland cement was reported used to plug this well.

RECEIVED  
KCC DIST # 3  
MAY 18 2016  
CHANUTE, KS

*RD*

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

*Ryan Duling*  
E.C.R.S.  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION  
MAY 23 2016  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*no  
6-13-16*