

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-20905-00-00
Spot: E2NESWSW Sec/Twnshp/Rge: 18-16S-32W
989 feet from S Section Line, 4068 feet from E Section Line
Lease Name: WELCH Well #: #1-18
County: SCOTT Total Vertical Depth: 4717 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4530		WITH 2 SX CMT
DVT	5.5	2347		WITH 275 SX CMT
PROD	5.5	4713	0	WITH 175 SX CMT
SURF	8.625	222		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2016 8:30 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: WADE KING Company: MURFIN DRILLING Phone: (785) 567-3004

Proposed
Plugging
Method:

GEL SPACER TO 2360' & CIRCULATE CMT TO SURFACE. TIE ONTO ANNULUS.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2016 1:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

SET CIBP @ 4530' WITH 2 SX CMT. RAN TBG TO 4498' & PUMPED 17 SX GEL. TBG AT 2368' CIRCULATED TO SURFACE WITH 200 SX CMT. TOPPED OFF WITH 20 SX CMT. BACKSIDE TO 5 SX CMT. PRESSURED TO 400 PSI.

Perfs:

Top	Bot	Thru	Comments
4583	4587		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed [Signature]
KCC WICHITA (TECHNICIAN)

RECEIVED
MAY 31 2016
KCC DODGE CITY

JUN 03 2016
RECEIVED

Form CP-2/3
20
6-13-16