


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

15-095-20134-0000

NORTH



Locate well correctly on above  
Section Plat

Kingman County, Sec. 31 Twp. 29S Rge. (E) 5 (W)  
Location as "NE/CNW/SW" or footage from lines. NE SW NW  
Lease Owner E. K. Edmiston Drilling Co., Inc.  
Lease Name Ewing Well No. 1  
Office Address 425 First Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 8, 1969  
Application for plugging filed 19\_\_\_\_  
Application for plugging approved 19\_\_\_\_  
Plugging commenced January 8, 1969  
Plugging completed January 8, 1969  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Ralph Warren of Pratt)

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4484 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	288'	8-5/8"	12/27/68	----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy Mud from Total Depth to 240 Feet;  
1/2 sax Hulls, Plug and 25 sax Cement thru  
the Drill Pipe; Mud to 40 Feet; 1/2 sax  
Hulls and plug bridged with Kelly and  
10 sax cement to Base of Cellar; 2 sax  
cement in Rat Hole. Job Completed at  
5:30 P.M. on 1/8/69.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 500 Bitting Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer  
500 Bitting Building, Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 10th day of January, 1969



Louise K. Whitted  
Louise K. Whitted - Notary Public.

15-095-20134-0000

DRILLERS LOG

EWING NO. 1

CASING RECORD:	OPERATOR: E. K. Edmiston Drlg. Co.	DESCRIPTION:
8-5/8" @ 288' w/200 sax cement	CONTRACTOR: Sage Drilling Co.	NE SW NW Sec. 31-29S-5W Kingman Co., Kansas
TOTAL DEPTH: 4484'	COMMENCED: December 27, 1968	ELEVATION: 1518KB
	COMPLETED: January 8, 1969	


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	290	
Red Bed & Shale	290	900	
Lime & Shale	900	2060	
Shale & Lime	2060	2790	
Lime & Shale	2790	3610	
Lime	3610	3955	
Lime & Shale	3955	4146	
Lime & Chert	4146	4460	
Lime & Shale	4460	4484	D&A

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Wayne W. Kahmeyer  
Wayne W. Kahmeyer



Subscribed and sworn to before me this 9th day of January, 1969.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1970.