


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Hodgeman County. Sec. 1 Twp. 24S Rge. XV 26(W)  
Location as "NE/CNW/SW" or footage from lines SE NW SE  
Lease Owner Iron Drilling Company  
Lease Name J. M. Schlereth Well No. 1  
Office Address 1206 Philtower Bldg., Tulsa, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-4-58 19\_\_  
Application for plugging filed " 19\_\_  
Application for plugging approved " 19\_\_  
Plugging commenced " 19\_\_  
Plugging completed " 19\_\_  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production None 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4886 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Toronto		4078		8-5/8	260	None
Lansing		4108				
Drum		4332				
Base of Kansas City			4541			
Marmaton		4558				
Cherokee		4678				
Detrital Zone		4781				
Mississippian		4794				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 250 feet. Set wood Plug & cement plug using 20 sacks  
of cement. Filled hole with heavy mud to 30 feet. Set cement plug using 10 sacks  
of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Iron Drilling Company  
Address 1206 Philtower Building, Tulsa, Okla.

STATE OF Oklahoma COUNTY OF Tulsa, ss.  
J. L. Stackpole (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. Stackpole  
Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of December, 19 58

My commission expires Feb. 28, 1960

B. Michal Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 20 1958

CONSERVATION DIVISION  
Kansas

PLUGGING  
FILE SEC L T 24 R 26 W  
BOOK PAGE 3 LINE 12

DRILLING RECORD

15-083-00171-0000

Well No. 1 Schlereth  
SE NW SE Sec. 1-24S-26W  
Hodgeman County, Kansas

Casing Record

260' of 8-5/8" OD Surface  
Pipe cemented with 175 sacks.

Work Commenced 11/13/58  
Drilling Commenced 11/14/58  
Drilling Completed 12/3/58  
Work Completed 12/4/58

No Oil String - Dry Hole

WELL LOG

Surface Soil, Sand & Clay	0 - 68
Gravel & Sand	68 - 98
Shale & Lime	98 - 260
Shale	260 - 710
Sand	710 - 915
Red Bed & Shale	915 - 1250
Sand & Shale	1250 - 1420
Shale & Lime	1420 - 1615
Shale	1615 - 1745
Lime	1745 - 1760
Lime & Shale	1760 - 2575
Lime	2575 - 2640
Lime & Shale	2640 - 3295
Lime	3295 - 3345
Lime w/ Shale Stks	3345 - 3425
Lime & Shale	3425 - 3518
Lime	3518 - 3585
Lime & Shale	3585 - 3840
Lime & Chalky Lime	3840 - 3925
Lime	3925 - 4055
Lime & Shale	4055 - 4090
Lime	4090 - 4795
Chert & Lime	4795 - 4818
Cherty Lime	4818 - 4839
Lime & Chert	4839 - 4855
Lime	4855 - 4886 TD

C E R T I F I C A T I O N

State of Oklahoma, County of Tulsa, SS.

I, J. L. Stackpole, Employee of Iron Drilling Company, certify that the accompanying is a true and correct log of the above described well.

*J. L. Stackpole*

Subscribed to and Sworn before me this 15th day of December, 1958

*B. Michal*

Notary Public

My Commission expires Feb. 28, 1960.

**PLUGGING**  
FILE SEC. 1, T. 24 R. 26W  
BOOK PAGE 3 LINE 12

**RECEIVED**  
STATE CORPORATION COMMISSION

DEC 20 1958

CONSERVATION DIVISION  
Tulsa, Kansas