

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County, Sec. 7 Twp. 24 Rge. 26 (E) W(W)

Location as "NE/CNW%SW%" or footage from lines SW SW SE

Lease Owner Barbara Oil Company

Lease Name Findlay-Keeley Well No. 1

Office Address 322 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 15 19 58

Application for plugging filed October 15 19 58

Application for plugging approved October 15 19 58

Plugging commenced October 15 19 58


Plugging completed October 15 19 58

Reason for abandonment of well or producing formation no oil in commercial quantities found

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4915 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	535'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 300'. Set Plug #1 at 300' with 20 sacks cement, 1/4 sx. Hulls. Filled hole with extra heavy rotary mud from Plug #1 to 40'. Set Plug #2 at 40' with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company

Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.R. McNicol
814 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of October, 1958

My commission expires Sept. 30, 1959

Darlene May
Darlene May Notary Public.

PLUGGING
FILE SEC 7 T. 24 R. 26w
BOOK PAGE 139 LINE 7

RECEIVED
STATE CORPORATION COMMISSION
10-22-1958
OCT 22 1958

CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLING LOG

OPERATOR: Barbara Oil Company
 FINDLAY-KEELEY ESTATE NO. 1
 SW SW SE Section 7-24-26W,
 Hodgeman County, Kansas

CONTRACTOR: Prime Drilling Company
 COMM: 9/26/58
 COMP: 10/15/58

Remarks: Set 8-5/8" surface casing
 at 535' cemented with 400
 sacks HA-5 Pozmix.

Formations:

Shale & Shells	400'
Sand	490'
Shale & Shells	1545'
Red Bed & Shale	1880'
Shale & Shells	2085'
Shale & Lime	2450'
Lime & Shale	2697'
Sandy Lime & Shale	2780'
Lime	3290'
Lime - Chalk	3355'
Lime & Shale	3465'
Lime	3599'
Lime Shale	3680'
Lime	3770'
Lime & Chalk	3832'
Chalk Lime - Shale	3845'
Chalky Lime	3860'
Lime Chalky	3930'
Chalky Lime - Shale	4020'
Lime	4075'
Chalky Lime - Shale	4161'
Lime	4249'
Lime & Chalk	4320'
Lime & Shale & Chalk	4370'
Lime	4428'
Lime - Shale	4544'
Lime	4720'
Lime - Shale	4761'
Lime	4814'
Lime & Chert	4850'
Lime	4871'
Lime & Chert	4915'
Rotary Total Depth (D&A)	4915'

We certify the above log is true
 and correct to the best of our
 knowledge and belief.

PRIME DRILLING COMPANY

R. R. McNicol

R. R. McNicol

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
FILE SEC 2 T 24 R 26W
BOOK PAGE 139 LINE 7