

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-069-20,183-0000

LEASE NAME Miller-Gray

WELL NUMBER 1

SPOT LOCATION C SE SE

SEC. 6 TWP. 24 S RGE. 29 W (E) (W)

COUNTY Gray

Date Well Completed 1-25-84

Plugging Commenced 1-25-84

Plugging Completed 1-25-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mustang Drilling & Exploration, Inc.

ADDRESS P.O. Box 1609, Great Bend, Ks 67530

PHONE # (316) 792-7323 OPERATORS LICENSE NO. 5652

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4955'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	457'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st plug @ 1900' w/ 50 sx, 2nd plug @ 960' w/ 50 sx, 3rd plug @ 500' w/ 40 sx, 40' bridge w/ 10 sx, rathole 15 sx; 165 sx 60/40 poz, 3% cc, 2% gel, plug down @ 5:30 a.m. 1-25-84

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mustang Drilling & Exploration, Inc. License No. 5652
Address P.O. Box 1609, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Bill Nelson (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill Nelson
(Address) P.O. Box 1609, Great Bend, KS

RECEIVED
STATE CORPORATION COMMISSION

2-21-84

FEB 21 1984
CONSERVATION DIVISION
My Comm. Expires _____

SUBSCRIBED AND SWORN TO before me this 10th day of February, 1984
NOTARY PUBLIC - State of Kansas
PAMELA K. WALTERS
My Appt. Exp. 8-25-87

Pamela K. Walters
Notary Public
Pamela K. Walters

August 25, 1987

ACO-1 Well History

Side TWO OPERATOR Mustang Drilling & Expl: LEASE NAME Miller-Gray SEC 6 TWP 24s RGE29W (W) (W)

WELL NO 1

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
Check if no Drill Stem Tests Run.				
Check if samples sent Geological Survey.				
Sand	0	466	Heebner	4023 -1218
Sand, Shale	466	1455	Toronto	4040 -1235
Sand	1455	1695	Lansing	4073 -1268
Sand, Shale	1695	1914	B/Kansas City	4515 -1710
Anhydrite	1914	1937	Marmaton	4530 -1725
Sand, Shale	1937	2098	Pawnee	4613 -1808
Shale	2098	2358	Ft. Scott	4639 -1834
Lime, Shale	2358	4955	Cherokee	4654 -1849
RTD		4955	Morrow Sd	4762 -1957
LTD		4958	Mississippi	4778 -1973
DST #1 4604-4627, times (30-45-60-45) Rec: 150' muddy water w/ show of oil, ISIP 1209, FSIP 115, IF 50/65, FF 65/79, Hyd 2300/2235.				
DST #2 4744-4473, times (30-60-60-45), ISIP 57, FSIP 50, IF 50/43, FF 43/43, Hyd 2314/2300, Rec: 15' mud.				

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1984

CONSERVATION DIVISION
Wichita, Kansas