

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Gray SEC. 7 TWP 24 S RGE. 29 E/W
Location as in quarters or footage from lines:
C-NE-NE

Lease Owner Thunderbird Drilling, Inc.
Lease Name Woolf "A" Well No. 1
Office Address P. O. # 97, Ellinwood, Kansas 67526
Character of Well (Completed as Oil, Gas or Dry Hole): oil
Date Well Completed 10-81
Application for plugging filed 8-5-83
Plugging commenced 11-15-83 12:15 P. M.
Plugging completed 11-15-83 1:45 P. M.
Reason for abandonment of well or producing formation

Locate Well
correctly on above
Section Platt.

depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation Morrow Depth to top 4762 bottom 4766 T.D. 4950
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	446	none
				4 1/2"	4863	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. No pipe recovery. Hole in casing at 1645. Squeezed with 250 sacks in December 1982. Allied Cementing pressured annulus to 600 #. Cement was to top. Mixed 1 sack hulls, 25 sacks of cement, 10 sacks jell, 50 sacks cement, 10 sacks jell, 75 sacks cement, & pumped down 4 1/2 casing. Left shut in with 1100 # pressure.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing & Thunderbird DRilling, Inc. #5131

STATE OF Kansas COUNTY OF _____, ss.
Maynard E. Weber (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maynard E. Weber
P. O. # 97, Ellinwood, Kansas 67526
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of Nov., 1983

Trevlyn Detmer
Notary Public

My Commission expires Barton County, Kansas
My Appt. Exp. Jan. 21, 1986

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1983
11-17-1983
CONSERVATION DIVISION
Wichita, Kansas