

15-083-20691-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Hodgeman SEC. 6 TWP. 24s RGE. 22w E/W
 Location as in quarters or footage from lines:
C of NE SW

Lease Owner Donald C. Slawson
 Lease Name Richter B #1 Well No. _____
 Office Address 200 Douglas Bldg., Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 2/11/83
 Plugging completed 2/15/83
 Reason for abandonment of well or producing formation _____
Depleted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4725'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	381'	none
				4 1/2"	4718'	3014'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged bottom with sand to 4450' & ran 4 sacks cement. Shot casing at
 3980', 3495', 3220', & 3015'. Pulled total of 72 joints. Squeezed hole
 with 3 sacks hulls, 15 sacks gel, 70 sacks cement, 1 sack hulls, & 15
 sacks gel, released plug & displaced with 130 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
 Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this _____ 18th day of _____ 1983



My Commission expires: _____

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 22 1983
 Notary Public.

CONSERVATION DIVISION
 Wichita, Kansas 2-22-98

WELL LOG

OPERATOR: DONALD C. SLAWSON
 200 DOUGLAS BUILDING
 WICHITA, KANSAS 67202

LEASE: #1 Richter 'B'
 C NE SW Sec. 6-24-22W
 Hodgeman County, Kansas

CONTRACTOR: SLAWSON DRILLING COMPANY, INC.
 200 DOUGLAS BUILDING
 WICHITA, KANSAS 67202

COMMENCED: November 30, 1979

COMPLETED: December 10, 1979

CASING: Surface - 8 5/8" @ 381' w/225 sx 60/40 poz
 Production - 4 1/2" @ 4718' w/100 sx 50/50 poz

- 0 - 383 Sand and shale
- 383 - 870 Shale and shells
- 870 - 1445 Sand and shale
- 1445 - 1463 Anhydrite
- 1463 - 1735 Sand and shale
- 1735 - 2260 Shale and shells
- 2260 - 3955 Lime and shale
- 3955 - 4472 Lime
- 4472 - 4510 Lime and shale
- 4510 - 4580 Lime
- 4580 - 4612 Mississippi - Lime
- 4612 - 4725 Lime
- 4725 RTD

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK) SS.

I, JAMES C. REMSBERG, OF THE SLAWSON DRILLING COMPANY, INC.
 UPON OATH STATE THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE
 LOG OF THE #1 Richter 'B' TEST.

James C. Remsberg

 JAMES C. REMSBERG, Engineer

SUBSCRIBED AND SWORN TO BEFOFE ME THIS 24th DAY OF January, 1980.

Sherry L. Kendall

 SHERRY L. KENDALL, Notary Public

MY COMMISSION EXPIRES: 6/12/82

SHERRY L. KENDALL
 STATE NOTARY PUBLIC
 Sedgwick County, Kansas
 My Appl. Exp 6/12/82

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 18 1980
 CONSERVATION DIVISION
 Wichita, Kansas