

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 12 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

9-12-1963

Dear Sir:

Mr. Dumham of Sunray DX Oil Company has this
 date requested permission to plug the following described well:

Mr. Dumham guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Company

Complete Address: 321 West Douglas. Wichita, Kansas

Lease Name: John Habiger Well No. 1

Location: C NW NE Sec. 26 Twp. 24S Rge. 22 (E) (W)

County Hodgeman Total Depth 4950' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dumham was instructed to plug the well as follows:

8 5/8"-273' Circulated w/cement.

Mud 4950' to 600' Spotted 25 Sax. cement 600' to 525'

Mud 525' to 270' Plug, Hulls, 25 Sax. cement 270' to 195'

Mud 195' to 40' Plug, Hulls, 15 Sax. cement 40' to surface.

Very truly yours,

Hugh Scott
 Conservation Division Agent