



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Glenn of Palomino has this

date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Palomino Petroleum

Complete Address: 304 Ins. Bldg., Wichita, Kansas

Lease Name: Hoffman Well No. 1

Location: C NE NW Sec. 36 Twp. 21 Rge. 22 (E) (W)

County: Hodgeman Total Depth 11765' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Glenn was instructed to plug the well as follows:

8 5/8" to 331' circulated w/ cement. 5 1/2" to 11760' cemented.

Top perforations 11753' Plug bottom w/ sand & 5 sacks cement.

Top of cement 1175' Mud 1175' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 330'

Spot 30 sacks cement 330' to 230' Mud 230' to 15'

Plug, Halls \approx 15 sacks cement 15' to 0'.

Very truly yours,

Conservation Division Agent