

State of Kansas



15-083-20006-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 10 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

4-10-1967

Mr. Lacey of Beardmore Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Lacey guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drilling Company

Complete Address: 700-120 Bldg., Wichita, Kansas

Lease Name: Erickson Well No. 1

Location: NW SW Sec. 10 Twp. 24 Rge. 23 (E) (W)

County Hodgeman Total Depth 4768' Oil Well X

Gas Well ___ Input Well ___ SWD Well ___ D & A X Lost Hole ___

Mr. Lacey was instructed to plug the well as follows:

- 8 5/8" to 316' circulated w/ cement. T.D. 4768'
- Mud 4768' to 700' Spotted 30 sacks cement 700' to 600'
- Mud 600' to 366' Spotted 30 sacks cement 366' to 266'
- Mud 266' to 45' Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,

Edward J. Green
Conservation Division Agent