

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSIONJAN 13 1975
1-13-75
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cameron of H-30 Drlg Inc has this

date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.Operator's full Name: Graves Drlg CoComplete Address: 910 Union Center Wichita, KSLease Name: Lecklider Well No. 1Location: C NE/SW Sec. 9 Twp. 29s Rge. 7 (E)(W)WCounty: Kingman Total Depth 4200 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Cameron was instructed to plug the well as follows:218 ft 8 5/8 surface cemented with 200 sacks. Pump plug,35 sacks cement to 210 ft. Mud to 40 ft, plug, 1/2 sackhulls, 15 sacks cement to surface. 2 sacks cement inrat hole.Pumped by Allied Cementing Great Bend, KS

Very truly yours,

Conservation Division Agent