

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD #2
K.A.R.-82-3-117

API NUMBER 15-095-97758

LEASE NAME Cunningham "B"

WELL NUMBER 8 SWD

440 Ft. from N Section Line

440 Ft. from E Section Line

SEC. 30 TWP. 27S RGE. 10W (E) or (W)

COUNTY Kingman

Date Well Completed 10-10-34

Plugging Commenced 9-3-88

Plugging Completed 9-7-88

LEASE OPERATOR Texaco Inc. for Texaco Producing Inc.

ADDRESS P.O. Box 2420, Tulsa, OK 74102

PHONE#(918) 560-6000 OPERATORS LICENSE NO. 4742

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 11, 1988 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Lansing Kansas City Depth to Top 3401' Bottom 3474 1/2' T.D. 3476'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				12 1/2"	321'	None
				5 1/2"	1111'	None
				7"	3401'	None

RECEIVED 10-27-1988
STATE CORPORATION COMMISSION
OCT 27 1988
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spotted sand on top of CIBP @ 3474 1/2 (top @ 3351'). Set cement plugs inside 7" csg. as follows: 3351-14' (7 sx), 2511-2446' (10 sx), 2012-1947' (10 sx), 1509-1444' (10 sx). Cemented 1165' to surf inside 7" csg. and 5 1/2" liner w/ 515 sx and cemented 12 1/2" - 7 1/2" annulus w/ 150 sx; cut off pipe, weld on plate, level location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Texaco Inc. for Texaco Producing Inc. License No. E14722

Address P.O. Box 2420, Tulsa, OK 74102

STATE OF OKLAHOMA COUNTY OF TULSA, ss. 11-16-88 11-16-88

John K. Hamby (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John K. Hamby

(Address) P.O. Box 2420, Tulsa, OK 74102

SUBSCRIBED AND SWORN TO before me this 25th day of October, 19 88

Elizabeth L. Legg
Notary Public

My Commission Expires: July 21, 1991