


15-095-20316-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 25 Twp. 29S Rge. 8 (X) 8 (W)

Location as "NE/CNW/SW" or footage from lines C W/2 SW/4

Lease Owner Aylward Drilling Co.

Lease Name Albright "B" Well No. 1

Office Address 909 First National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 3, 1973

Application for plugging filed August 3, 1973

Application for plugging approved August 3, 1973

Plugging commenced August 3, 1973

Plugging completed August 3, 1973

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4235 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	247'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 245 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1973
CONSERVATION DIVISION
Wichita, Kansas
08-13-73

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
505 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 1973

My commission expires May 9, 1975
Betty Brandt Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Aylward Drilling Co. DRILLING COMMENCED: July 27, 1973
909 First Nat'l. Bank Bldg.
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: August 3, 1973
505 Union Center
Wichita, Kansas 67202

CASING RECORD: 6 Jts. 247' 8-5/8" LOCATION: Albright "B" No. 1
cemented with 200 sacks. C W/2 SW/4
Section 25-29S-8W
Kingman County, Kansas

0 - 248	Red bed & shale
248 - 630	Shale
630 - 1199	Shale & shells
1199 - 1410	Lime & shale
1410 - 1890	Shale & lime
1890 - 2120	Lime & shale
2120 - 2485	Shale & lime
2485 - 2965	Lime & shale
2965 - 3519	Shale & lime
3519 - 4060	Lime
4060 - 4140	Lime & shale
4140 - 4206	Shale & lime
4206 - 4235	Chert & lime
4235	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1973
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John Graves* President

STATE OF KANSAS)
) ss.
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 9th of August, 1973.

My commission expires:
May 9, 1975

Betty Brandt
Betty Brandt Notary Public