

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Kansas Corporation Commission  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-069-20,265-0000

LEASE NAME Hands

WELL NUMBER #1

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 10 TWP. 24S RGE. 30 (E) or (W)

COUNTY Gray

Date Well Completed 09-06-97

Plugging Commenced 09-05-97

Plugging Completed 09-06-97

SEP 23 1997 NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

CONSERVATION DIVISION  
WICHITA, KS

LEASE OPERATOR Knighton Oil Company, Inc.

ADDRESS 221 S. Broadway, #710, Wichita, KS 67202

PHONE/(316) 264-7918 OPERATORS LICENSE NO. 5010

Character of Well D/A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09-05-97 (date)

by Steve Middleton (XCC District Agent's Name).

Is ACO-1 filed? Enclosed If not, is well log attached?

Producing Formation N/A Depth to Top  Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	249'	8 5/8"	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from    feet to    feet each set. Fill with heavy mud. 1st plug from 2045'-1845' with 50 sks, 2nd plug from 1030'-710' with 80 sks, 3rd plug from 550'-390' with 40 sks, 4th plug from 260'-100' with 40 sks, 5th plug from 40'-0' with 10 sks. Rat hole with 15 sks, cemented with 235 sks 60/40 pos, 6% gel, 1/4# floeal per sk.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

David D. Montague (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 221 S. Broadway, Suite 710  
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 97

[Signature]  
Notary Public

My Commission Expires: 12/11/97

Sarah A. Simon

