

RECEIVED

OCT 09 2001

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Gordon Schmidt

WELL NUMBER 1

3960 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 35 TWP. 23 RGE. 4 (E) or (W)

COUNTY Reno

Date Well Completed 1-23-1997

Plugging Commenced 9-17-2001

Plugging Completed 9-18-2001

LEASE OPERATOR Excalibur Prod. Co. Inc.

ADDRESS 1016 N main P.O. Box 278 McPherson, Ks.

PHONE (316) 241-1265 OPERATORS LICENSE NO. 5330

Character of Well good oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 9-17-2001 (date)

by Mr. Mike Wilson (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? yes

Producing Formation Mississian Osage Depth to Top 3303 Bottom 3315 T.O. 3350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13 3/8	284	0
				8 5/8	604	0
				5 1/2	3349	2000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material was used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Sand bottom off from 3346 to 3260 Dump 5 sack at 3260' to 3218'

Ripped casing at 2520' Worked casing stuck ripped at 2300' work casing stuck

Ripped casing at 2000' worked casing free Pulled to 666 ft Spot 50 sack 60-40 4% gel

Pull casing to 344' circulated cement to surface and pull casing fill 8 5/8 to top

9-21-2001 cement down 120' fill with 35 sack cement

Name of Plugging Contractor Sun Flower well service License No. 30280

Address 408 N 4 Canton, Kansas 67428

Name of Party Responsible for Plugging Fees: Excalibur Prod. Co. Inc.

State of Kansas COUNTY OF McPherson 67460, ss.

Dennis Gordley

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.


(Signature) Dennis D. Gordley

(Address) 1108 Glendale McPherson Ks.

SUBSCRIBED AND SWORN TO before me this 5th day of October 2001

Juanita M. Flood
Notary Public

My Commission Expires: 5/27/04



OR