

15-155-20985-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado De-By Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER May 4, 1984
LEASE NAME Branden Berger
WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line
1650 Ft. from ^W/₄ Section Line

LEASE OPERATOR Excalibur Prod Co Inc.
ADDRESS 523 W. Kansas Box 278 McPherson

SEC. 35 TWP. 23 RGE. 4W (E) or (W)
COUNTY Reno

PHONE# (916) 241-1265 OPERATORS LICENSE NO. 5330

Date Well Completed May 84

Character of Well Oil

Plugging Commenced 9-9-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-18-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Miss Depth to Top 3332 Bottom 3338 T.D. 3355

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				12 3/4	247	0
				9 5/8	584	0
				5 1/2	3355	3100

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dumped sand to 3290, Dumped 5 sack cement w/ dump batter, shot + pulled pipe, built bridge 350" filled to surface w/ Redi Mix welded on cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Oil Field Serv Inc. License No. 3004

Address Box 607 Burnton KS 67020

STATE OF KS COUNTY OF Harvey, ss.

Ed Gressel

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Ed Gressel

(Address) Box 607 Burnton KS 67020

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 19 86


Mary W. Klein
Notary Public

My Commission Expires: March 15, 1989



Rec'd 23-86

SEP 23 1986



Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

May 4, 1984

15-155. 20985-0000

COMPANY: BLACKSTONE DRILLING, INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: BRANDENBERGER #1
 LOCATION: 330' FSL & 1650' FWL SW/4 Section 35-23-4W,
 Reno County, Kansas
 COMMENCED: April 20, 1984
 COMPLETED: May 4, 1984
 ELEVATION:

0	to	145	Sand
145	to	600	Salt
600	to	1310	Lime & Shale
1310	to	1805	Shale
1805	to	2797	Shale & Lime
2797	to	3145	Lime & Shale
3145	to	3250	Lime
3250	to	3315	Shale & Lime
3315	to	3355	Mississippi
		3355	T. D.

Cut 12 1/2" hole to 246' and run 248' of 12 3/4" casing, cemented with 200 sacks of cement at 246'. Plug down at 2:10 P. M., April 20, 1984. Run 584' of 8 5/8" casing, cemented with 250 sacks of cement at 582'. Plug down at 2:30 P. M., April 26, 1984. Run 3356' of 5 1/2" casing, cemented with 3350' with 75 sacks of cement Plug down at 2:15 P. M., May 4, 1984.

TOPS: MISSISSIPPI - 3272'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Brandenberger #1, located on the SW/4 Section 35-23-4W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.


 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 4th day of May, 1984.


 Johnnie L. Schmidt - Notary Public

