

To: 2 040374  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

11-9-87  
API NUMBER 15- 095-21-149- 21419-0000

C. SE. SE. SEC. 10, T. 29 S, R. 6 WXX

660 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5348

Lease Name Clayton Well # 1

Operator: Robert E. Campbell

County Kingman 144.79

Name & Address 260 N. Rock Road, Suite 110

Well Total Depth 4455 feet

Wichita, KS 67206

Conductor Pipe: Size 4 1/2" feet 4159

Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address Great Bend, KS 67530

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pulling (phone) \_\_\_\_\_

were: Perfs @4039-46 300# hulls, 10 sxs gel, 100 sxs 60/40 poz

Plugging Proposal Received by J. L. Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 10:50 Day: 9 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT Sand was dumped inside the 4 1/2" casing to 3990' and capped with 4 sxs cement. The 4 1/2" was shot off and recovered. The top was squeeze plugged by pumping 300# hulls, 10 sxs gel, and 100 sxs of 60/40 poz cement.

Remarks: B.J. Titan MX 700# SI 300# #407828

A.S.C. (If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

INVOICED

(If applicable) observe this plugging.

NOV 12 1987

Signed *John Sanders* (TECHNICIAN)

DATE 11-20-87

INV. NO. 18923

CONSERVATION DIVISION  
Wichita, Kansas