

7-11

184
R

2-040543

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-095-21411-0000
SECTION 7 TOWNSHIP 29 RANGE 6W

OPERATOR LICENSE # 5171 1980 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR TXO Production Corp.
NAME & ADDRESS 1660 Lincoln St., #1800
Denver, CO 80264

LEASE NAME: Kaufman #A-1
COUNTY: Kingman
WELL TOTAL DEPTH: 4230' - 137.48
CONDUCTOR PIPE: " @ "
SURFACE CASING: 8-5/8" @ 264'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Clark Corporation
ADDRESS: Medicine Lodge LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Elmo Morganstien
COMPANY NAME: Clark Corporation PHONE: _____

WERE: 4-1/2" @ 4224' - perfs 4130-50' - rec. 3200' - sand to
4025' & 4 sx - 25 sx @ 507'

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

JUL 23 1990 07-23-90

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

CONSERVATION DIVISION

COMPLETED: HOUR: 15:00 DAY: 11 MONTH: 7

Wichita, Kansas
YEAR: 1990

ACTUAL PLUGGING REPORT:

The perfs were sanded back to 4025' & capped w/4 sx
cmt - 4-1/2" was recovered from 3200' & pulled from
well bore - 2-3/8" tubing run in hole to 792' where 35
sx cmt spotted - tubing pulled to 507' where 25 sx
spotted - tubing pulled to 317' & circ back to surf -
well went on vacuum and additional 100 sx was circ from
253'

REMARKS: B. J. Titan 60/40 4% gel & comm

I DID OBSERVE THIS PLUGGING.

INVOICED

Steve Van Gieson
Steve Van Gieson (AGENT)

DATE: 7-20-90

INV. NO. 28802

FORM CP-2/3
REV. 3/90

nb