

2 050387

API NUMBER 15- 095-01,001 0001

SEC. 6, T 29 S, R 6 (W/E)

660 feet from S section line

660 feet from E section line

Lease Name Graber (OWWO) "C" Well # 1

County Kingman 134.45

Well Total Depth 4137 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 223

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number

Address

Company to plug at: Hour: Day: 9 Month: 5 Year: 19 86

Plugging proposal received from

(company name) (phone)

were: 4 1/2" casing set at 4132' with 150 sacks of cement - perf at 4044-4058 -

sand back to 3925 and dump 4 sacks of cement - shoot and pull pipe

Plugging Proposal Received by G.W. (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:15 p.m. Day: 13 Month: 5 Year: 19 86

ACTUAL PLUGGING REPORT Sanded back to 3925 feet and dumped 4 sacks of cement. Shot

and pulled 3011 feet of 4 1/2" casing. Squeezed 8 5/8" with 15 sacks of gel, 1 sack of

hulls and 75 sacks of 60/40 with 4% gel. Squeezed at 400# closed in

STATE CORPORATION COMMISSION

MAY 22 1986 05-2286

CONSERVATION DIVISION Wichita, Kansas

Remarks: B.J. Titan 283236 (If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAY 22 1986

INV. NO. 13945

WK

Signed Glenn L. Wray (TECHNICIAN)

BO