

1080223

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,160-0000

W/2 SE NW, SEC. 4, T 24 S, R 26 W/2

1980 feet N SE Corner of ~~W/2~~ section line
3520 feet W SE Corner of ~~W/2~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9641

Lease Name Burr Well # 1

Operator: Stauffer Oil & Gas Exploration

County Hodgeman

Name & Address 600 17th Street, Suite 1600S

Well Total Depth 4925 160.06 feet

Denver, CO 80202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sage Drilling Company License Number 5421

Address 202 South Street Francis, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 21 Month: September Year: 19 84

Plugging proposal received from Terry Maxwell

(company name) Sage Drilling (phone) 316-263-6139

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1780' with 50 sx cement

2nd plug at 900' with 50 sx cement

3rd plug at 310' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement. Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:00 am Day: 21 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1780' with 50 sx cement, 2nd plug at 900' with 50 sx

cement, 3rd plug at 310' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx

cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 01 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Dowell

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

10-1-84

Should you observe this plugging.

INVOICED

Signed J. H. Metz (TECHNICIAN) SD

DATE 10-8-84

INV. NO. 4078

FORM CP-2/3
Rev. 01-84