

To: 1 120560
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-3 390
API NUMBER 19- 069-20,243-0000
C SE NE, SEC. 9, T 24 S, R 29 W/2

TECHNICIAN'S PLUGGING REPORT

Operator License # 6668

Operator: Theodore I. Leben
Name & Address: 105 S. Broadway, Suite 640
Wichita, KS 67202

3300 feet from S section line
660 feet from E section line

Lease Name Collingwood Well # 1-9

County Gray 159.25

Well Total Depth 4900 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 473

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 3 a.m. Day: 3 Month: 5 Year: 19 91

Plugging proposal received from Jay

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1798-1827'
1st plug at 1870' with 50 sx cement, 2nd plug at 900' with 50 sx cement,
3rd plug at 500' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:30 a.m. Day: 3 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1870' with 50 sx cement,

2nd plug at 900' with 50 sx cement,

3rd plug at 500' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 06 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy) do not observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 5-28-91

INV. NO. 31870