

1060219

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-069-20,125-0000

C NW NW, SEC. 9, T 24 S, R 29 W

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5533

Lease Name Wendall Well # A-1

Operator: Arrowhead Petroleum, Inc.

County Gray

Name & Address Box 1393

Well Total Depth 4900 189.25 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 405

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Dowell License Number _____

Address West Railroad Avenue, Great Bend, KS 67530

Company to plug at: Hour: 9:00 am Day: 17 Month: April Year: 19 84

Plugging proposal received from A. D. Beltz

(company name) Arrowhead (phone) 316-793-6656

were: 4 1/2 set at 4899 Perfs 4742 - 46 Squeezed at 1363' to 96'

1st plug pumped through 4 1/2 with 1 sx hulls, 20 sx cement, 10 sx gel, 30 sx cement,

10 sx gel, 1 sack hulls and 100 sx cement. Bled pressure off & refilled hole to surface.

Annulus would not take any cement. We tried to pump in and pressured up to 500#.

Maximum pressure 800# shut in pressure 0

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:59 am Day: 17 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4899' Perfs 4742-46 Squeezed at 1363' to 96'

1st plug pumped through 4 1/2" with 1 sack hulls, 20 sx cement, 10 sx gel, 30 sx cement,

10 sx gel, 1 sack hulls and 100 sx cement. Bled pressure off & refilled hole to surface.

Annulus would not take any cement. We tried to pump in and pressure up to 500#.

Maximum pressure 800# and shut in pressure 0#.

Remarks: Used Class A Cement by Dowell.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE 4-20-84

APR 20 1984

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 1182

CONSERVATION DIVISION Wichita, Kansas

4-17 MAY 03 1984

FORM CP-2/3 Rev. 01-84