

1 120615

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-24  
API NUMBER 15- 069-20,244-0000

E/2 NE NE, SEC. 16, T 24 S, R 29 W/E

4620 feet from S section line

330 feet from E section line

Lease Name Woodford-O'Brate Well # 1-16

County Gray 162.50

Well Total Depth 5000 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Chief Drilling, Inc. License Number 5886

Address 224 E. Douglas, Suite 350, Wichita, KS 67202

Company to plug at: Hour: 1 p.m. Day: 24 Month: 8 Year: 19 91

Plugging proposal received from Harold Dinkel

(company name) Chief Drilling, Inc. (phone) 316-262-3791

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1960-84'

1st plug at 2000' with 50 sx cement, 2nd plug at 1000' with 80 sx cement,

3rd plug at 500' with 30 sx cement, 4th plug at 330' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 7:30 p.m. Day: 24 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2000' with 50 sx cement,

2nd plug at 1000' with 80 sx cement,

3rd plug at 500' with 30 sx cement,

4th plug at 330' with 50 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 11 1991

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED  
(check) (did not) observe this plugging.

DATE 9-18-91

INV. NO. 33162

Signed Duane Rankin (TECHNICIAN)