

1 050821

2362

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,058-0000  
S/2 SE SW, SEC. 6, T 24 S, R 22 (W/E)  
330 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181  
Operator: Donald C. Slawson  
Name & Address: 200 Douglas Building  
Wichita, KS 67202

Lease Name Richter Well # C-1  
County Hodgeman 153.73  
Well Total Depth 4730 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:00 pm Day: 27 Month: June Year: 19 86

Plugging proposal received from Vernon Duntz  
(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4729' Perfs at 4500-4504'; 4590-4594'

1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer

2nd plug pump 2 sx hulls and 150 sx econolite

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:45pm Day: 27 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls and 150 sx cement.

Maximum pressure 500 psi and shut in 100 psi

Remarks: Recovered 2800' 4 1/2" casing. Used Halcolite by Halliburton  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE JUL 10 1986  
INV. NO. 14331

RECEIVED  
STATE CORPORATION COMMISSION  
Signed Richard W. Lacy (TECHNICIAN)  
JUL - 8 1986 7-8-86