

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-083-20,691-6000 R  
CNE SW, Sec. 6, T 24 S, R 22 W  
\_\_\_\_\_ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Richter 'B' Well # 1 R

Operator: Donald C. Lawson  
Name & Address 200 Douglas Building  
Wichita Kansas 67202

County Hodgeman

Well Total Depth 4725 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 381 W/2255V

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pullers License Number 6050

Address Box 176 Chase KS. 67524 Rig # 548

Company to plug at: Hour: 9:00 Day: 15 Month: Feb Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Buck Unruh

(company name) Kelso Casing Pullers (phone) \_\_\_\_\_

were: 50/50 poz mix 4% gel 3% cc

1st plug sanded to 4450 + W/4 sx

2nd plug 3 hulls - 15 gel - 70 sx cement - 15 gel -

1 hull - wiper plug - 130 sx cement

Halliburton Cemented

Signed Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 Day: 15 Month: Feb Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered in above paragraph

Max Pump Pressure 500 psi

Shut in Pressure 300 psi

Recovered 3015' of 4 1/2" production string

Remarks: Steve Durrant gave orders

RECEIVED  
STATE CORPORATION COMMISSION

FEB 17 1983

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as stated and that I (did / ~~did not~~) observe this plugging.

2-17-83

Signed Richard W. Lacey  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

INVOICED  
MAR 24 1983

DATE \_\_\_\_\_

INV. NO. 36794